



- KEY NOTES**
- 1 NEW RETURN AIR TRANSFER OPENING WITH FIRE DAMPER AND SECURITY MAN BARS.
  - 2 CONTRACTOR TO RELOCATE EXISTING ACU-2-1 AS SHOWN.
  - 3 DISCONNECT CHILLED WATER PIPING FROM EXISTING AFTER HOUR CHILLER AND RECONNECT TO EXISTING CHILLED WATER RISER IN MECHANICAL ROOM.

- GENERAL NOTES**
- 1. CONTRACTOR TO CLEAN AND REUSE EXISTING GRILLS WHERE POSSIBLE. CONTRACTOR TO VERIFY COUNT PRIOR TO BIDDING.
  - 2. LANDLORD TO APPROVE ALL T-STAT LOCATIONS PRIOR TO DRYWALL INSTALLATION.

FLEX SCHEDULE	
6"	50-125 CFM
8"	130-200 CFM
10"	205-330 CFM
12"	335-450 CFM
14"	455-600 CFM
16"	605-700 CFM

MECHANICAL PLAN  
1/8"=1'-0"

ISSUED FOR REVIEW	
KAMM CONSULTING PROJECT # 3013-0764 PROJECT MANAGER: DUANE MILLAR	
<b>KAMM Consulting</b> 1408 Orange Avenue Fort Pierce, Florida 34950 Phone 772.595.1744 Fax 772.595.1745 engineering@kammconsulting.com Certification of Authorization #8189	
PRINCIPAL Brady L. Brown	Florida License #58232
date	signed

ALLEGIANCE MARKETING GROUP  
FAIRWAY OFFICE CENTER  
7111 FAIRWAY DRIVE #205  
PALM BEACH GARDENS, FL 33418  
PROJECT NUMBER 711119

REVISIONS

1	
2	
3	
4	
5	

THIS DESIGN AND THESE DRAWINGS ARE THE PROPERTY OF KAMM CONSULTING. NO PART OF THIS WORK MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT PERMISSION IN WRITING FROM KAMM CONSULTING INC.

DRAWN BY ASB

CD

10/01/13

M2.1

birse design inc.  
5900 woodland lakes drive  
palm beach gardens, fl 33418  
phone 561-249-4001  
fax 772-402-8884  
A426001615

Bd

MECHANICAL PLAN